



Continental HHT Update Client


Instructions to Update the Hand-Held Tool

**(only for Continental Internal
employees)**


Download and Update Installation Instructions

1. Installation


- › Request software installation in SSP7, in the following link:
 - › <http://ssp.auto.contiwan.com/SSP6/Forms/form.aspx?id=1942>
- › Select your laptop hostname.



- › Search with “Hand-Held Tool Update Client”, select the software and submit the ticket.




- › After IT ticket is completed, go to Portal Manager and launch “Hand-Held Tool Update Client”.



2. Update Process

- › Open “Hand-Held Tool Update Client” software and follow the instructions displayed. The update client will update itself on every launch.




- › The update client will automatically download the latest Hand-Held Tool software from the internet and stores in the PC. An offline update is possible with the downloaded software packages.
- › In case the Hand-Held Tool
 - › has a Firmware version is inferior to 6.8 or (check menu “Setup → Release” on your Hand-Held Tool device)
 - › is not detected or is not responsive

Then follow the instructions below

- › Power off the device (if not possible, press the reset button)
- › Keep the ESC button pressed, connect the USB cable to the PC and to the Hand-Held Tool
- › Launch the “Hand-Held Tool Update Client” software and follow the instructions displayed.

2. Settings for internet connection (Proxy settings)

- › In case the user is in the Continental network or connected via VPN, the default proxy settings are applied.
 - › If this does not work, then try “No Proxy” and press “Confirm”.
- › In case the user is outside the Continental network, select “No Proxy” and press “Confirm”.



3. Troubleshooting

- › The client might hang or not detect the Hand-Held Tool due to the following reasons:
 - › Application is run without drivers being installed.
 - › Defective USB cable
 - › Unstable USB connection due to some software issues on the computer.
 - › Earlier update process interrupted.
- › Resolve the problem:
 - › The user should close the application and restart it again.
 - › Try a different USB port.
 - › If the behavior is still the same, please open an IT ticket, to support group: TI WW ContiConnect DEVICE and CONNECTIVITY RnD / Category TI ContiConnect (BMC service).

4. Uninstall old version

(only if you have previous tried to install HHT Update Client and you were not successful)

- › Uninstall the previous version, by:
 - › Go to Control panel app → *Programs and features*
 - › Call IT and ask to remove “*Continental HHT Update*” and “*Window USB drivers Tecnomotor...*”
 - › If you don't have admin rights or IT hotline wants you to raise a uninstall request in SSP7 then follow this link:
<http://ssp.auto.contiwan.com/SSP6/Forms/form.aspx?id=1263>
 - › Delete C:\Continental folder if it still exists.

Continental Reifen Deutschland GmbH

Büttnerstraße 25

30165 Hannover

Germany

www.continental-truck-tires.com

www.continental-corporation.com

